Mobile Home Site Assessment Conduct site assessment (SWS 2.0402.2) **Moisture Assessment Installation Assessment** - Standing Water (SWS 2.0111.5) - Positive Grade - Settling of the home - Condition of Gutters - Leveling of the home Vegetation/Shrubbery - Organic materials [DLI MH Bulletin #44] Can weatherization proceed without deferral? No: Defer Yes: Proceed Yes, with Remediation* Can WAP remediate? No: Defer Yes: Proceed *All remediation activities must follow the AMC Created: June 2016 Minnesota Weatherization Assistance Program