BLUE EARTH CO.
R-27-W
R-26-W
SECTION 24
SECTION 19
SECTION 20
SECTION 21
SECTION 22
SECTION 23
SECTION 25
SECTION 30
SECTION 29
SECTION 28
SECTION 27
SECTION 26
SECTION 35
SECTION 36
SECTION 31
SECTION 32
SECTION 33
SECTION 34
MANKATO MUNICIPAL AIRPORT
238 STR (LIME 305)
231 STR (LIME 231)
COUNTY HIGHWAY NO. 2 (200 AVE)
COUNTY ROAD 183 (GRAND)
LIME VALLEY ROAD (GRAND AVE)
OLD STATE HWY NO 22
COUNTY HIGHWAY NO. 10
LOCATION 1
BEGIN PROPOSED 20" MANKATO ENERGY CENTER PIPELINE
LOCATION 2
RAILROAD SPUR, APPROX. 300' BORE TO CROSS.
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-1
LOCATION 3
COUNTY ROAD 183, APPROX. 100' BORE TO CROSS.
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-2
LOCATION 4
HWY. 22 DOUBLE LANES WITH STORM WATER DRAIN DITCH APPROX. 400' DIR. DRILL TO CROSS.
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-3
LOCATION 5
OLD HWY. 22, APPROX. 150' BORE TO CROSS.
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-4
LOCATION 6
SMALL TREES AREA, APPROX. 200' OPEN CUT, APPROX. 20' ELEVATION CHANGE.
LOCATION 7
LARGE TREES, MIX WITH 6" TO 24" DIAMETER TREES, APPROX. 1 MI. LONG WITH 100' ELEVATION CHANGE, HALFWAY TO 2000' SECTION, OPEN CUT.
LOCATION 8
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-5
GRAVEL COUNTY ROAD, APPROX. 150' OPEN CUT AT START OF 300' ELEVATION RISE SINGLE TREE, APPROX. 200' WEST OF SEC. 8 AND WEST OF THE END OF SEC. 7 WITH DRAW IN THE MIDDLE.
LOCATION 9
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-6
TWO RAILROAD TRACKS, LENGTH TO CROSS BOTH TRACKS IS APPROX. 200', CAN BE CROSSED IN ONE BORE.
LOCATION 10
HWY. 2, APPROX. 200' BORE TO CROSS.
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-7
LOCATION 11
HOUSE TRACK, APPROX. 50' BORE TO CROSS.
LOCATION 12
R.R. SPUR, APPROX. 50' BORE TO CROSS.
FOR TEMP. WORK SPACE SEE CPNDV-3014-P9-8
PROPOSED LOCATION OF N.N.G.'S PROPOSED TAP VALVE
PROPOSED N.N.G. LATERAL
PROPOSED CALPINE MANKATO ENERGY CENTER - N.N.G. METER STATION SITE (130'x250') (RED LINE)
PROP. 20" MANKATO ENERGY CENTER PIPELINE ROUTE, APPROX. 8,508± (FEET).
PROPOSED LOCATION OF THE MANKATO ENERGY CENTER PLANT
PROPOSED MANKATO ENERGY CENTER PLANT SITE (50' WIDE x 1330' LENG.)
75' POWERLINE R/W
50' PERMANENT R/W
O.H. POWER LINE
CEMETERY
LARGE TANK (WATER/SANITARY)
NORTHERN NATURAL GAS
T-109-N
NOTE:
SECTION LINE AND PROPOSED GAS PIPELINE ROUTE ARE SHOWN AT APPROXIMATE LOCATION.
LEGEND
CALPINE MEC 20" GAS PIPELINE
CALPINE 50' PERMANENT R/W
CALPINE 25' TEMPORARY WORK SPACE
CALPINE ADDITIONAL TEMPORARY WORK SPACE
O.H. POWER LINE
POWERLINE R/W
600' 0 600' 1200' 1800' 2400'
GRAPHIC SCALE
CALPINE-MANKATO ENERGY CENTER
PROPOSED NATURAL GAS PIPELINE ROUTE
DATED: 8-27-2004